







Your engagement in this process is important to the success of this project, so thank you for taking the time to be here today!





### **Kansas Department of Agriculture**

Joanna Rohlf, CFM, GISP

Floodplain Mapping Coordinator

William Pace, CFM
Floodplain Mapping
Specialist

**Keegan Schwartz** *Floodplain Outreach Specialist* 

Tara Lanzrath, CFM
State NFIP Coordinator

Cheyenne Sun Eagle, CFM NFIP Specialist

FEMA – Region VII

Dawn Livingston

Regional Project Officer

WSP USA Environment & Infrastructure Inc.

Ben Rufenacht, PE, CFM
Project Manager /
Engineer

Erika Stanley Sr. GIS Analyst



### Today's Goals

Share details on the mapping project

Get initial feedback on modeling methods


Review future steps



### **Background**

It was determined that updated modeling and mapping for portions of Barton County using newer Lidar and 2D modeling techniques, would be beneficial.

- Barton County Effective Mapping
  - PMR completed in 9/15/2019 for the Cow Watershed
  - Remainder of the county maps are dated 9/2/2009
- Lower Middle Arkansas Custom Watershed BLE
  - Discovery Meeting held on 1/12/2021 & 1/13/2021
- Middle Smoky Hill Custom Watershed BLE
  - Discovery Meeting held on 3/10/2021
- Pawnee-Walnut Custom Watershed BLE
  - Discovery Meeting held on 7/26/2023
- Upper Middle Arkansas Custom Watershed BLE
  - Discovery Meeting held on 12/12/2023




### **Definitions**




**Hydrology** *How Much Water?* 



Hydraulics
How High Will Water Get?




- · Fluvial flooding only. · Data along studied streams.
- · Event-based analyses.







- Fluvial and pluvial flooding.
- · Data for entire watershed.
- · Probabilistic analyses.




- Enhancements will be made to the BLE modeling that was performed.
  - Lidar, flown in 2018, will be used.
  - Comments made will be used to enhance the modeling.
  - Additional review/refinement of mesh will be done to improve accuracy of modeling.
  - Enhanced Zone A, Zone AE with Floodway, Zone AE without Floodway, and Zone AH on selected streams will include field surveyed structure data, as-built survey plans, and additional land use refinements.




- The hydrology is built into the RAS modeling platform using excess rain-on-mesh modeling.
- HEC-RAS calculates the excess rainfall using NRCS Curve Number methodology.
- Details added to 2D mesh as needed.
- Add detail to significant flood control dams as needed.
- Model flows will be compared to Kansas regression flows and gage (where available) for validation.




- Refined Mesh
  - Will allow for greater accuracy in flood modeling due to increased cell density






### Refined Land Use


Will allow for greater accuracy in surface modeling due to more detailed land use








- Detailed structure modeling incorporated into Refined models, where data is available
  - Do you have any recent structure improvements, or planned improvements, that has data that can be shared?

Field collected structure data, if necessary













A Floodway is the area within the floodplain that must be reserved in order to discharge the base flood without cumulatively increasing the WSE by more than 1.0 foot.











### **Scoped Studies**

#### New Zone A - Excess Rainfall on Grid

New Zone A studies will be developed for these streams using 2D "excess rainfall-on grid" hydrology and 2D Hec-Ras hydraulics.

#### New Zone A - Gage Analysis

New Zone A studies will be developed for these streams using 2D Hec-Ras hydraulics and hydrology calibrated to Gage Analysis flows.

### New Zone AE with Floodway - Gage Analysis

New Zone AE studies will be developed for these streams using 1D or 2D Hec-Ras hydralics and hydrology calibrated to Gage Analysis Flows. Floodways will be developed. Field measured structure data will be incorporated into the modeling. BFEs will be shown on the maps.

#### New Zone AH - Excess Rainfall on Grid

New Zone AH studies will be developed for these streams using 2D Hec-Ras hydralics and "excess rainfall-on grid" hydrology. Field measured structure data will be incorporated into the modeling. BFEs will be shown on the maps.


#### New Zone AH - Gage Analysis

New Zone AH studies will be developed for these streams using2D Hec-Ras hydralics and hydrology calibrated to gage analysis flows. Field measured structure data will be incorporated into the modeling. BFEs will be shown on the maps.

### New Enhanced Zone A - Excess Rainfall on Grid


New Enhanced Zone A studies will be developed for these streams using 2D "excess rainfall-on grid" hydrology and 2D Hec-Ras hydraulics. Field measured structure data will be incorporated into the modeling.

### Incorporation of Existing Studies from the Cow Watershed project




# New Zone AE with Floodway New Zone AH for Wet Walnut Creek

### **Albert**



## Effective Zone AH is between Walnut Creek and Dry Creek 21

### **Albert**



### New Zone AE with Floodway for Arkansas River Enhanced Zone As 22

### **Ellinwood**




### Zone AE with floodway on Arkansas River

New Zone AE
without floodway for
West Walnut
Diversion Channel

New Enhanced Zone
As

### **Great Bend**




# New Zone AH for Ash Creek Tributaries A and B


### Pawnee Rock




# New Zone AH for Ash Creek Tributaries A and B

### Pawnee Rock








# Incorporation of Existing Studies for Cow Watershed


### **Barton County**



### Levees


### There are 7 levees in the project area.






- Great Bend Levee North Side & Walnut NW
- Great Bend Levee Little Walnut W & Airport Ring
- Great Bend Levee South Side







 Agricultural levees near Ellinwood



Agricultural levee near Albert




### Field Survey Base Map Terrain Collaborative Partnerships **Development** Updated Hydrologic and Hydraulic Modeling Floodplain Mapping Draft FIRM Database FIRM & FIS Production Post-Processing Map Adoption

### Project Tasks


- Field Survey
- Base Map and Topography Preparation
- Hydrologic and Hydraulic Modeling
- Floodplain Mapping
- DFIRM and FIS Production
- Post-Preliminary

We are about to begin the modeling task

**Data** 



- We will complete the engineering analysis previously described.
- Several rounds of reviews will be completed.
- We will develop your draft regulatory floodplain maps.
  - Also known as your Flood Insurance Rate Map (FIRM)
- We will develop your draft Flood Insurance Study (FIS).
- We will have a community review period and a public review period



We will also be developing flood risk products for the studied areas in Barton County as part of this project.

\*Data and tools that can help you plan for ways to reduce your community's flood risk.

Water Surface Elevation Grids



Water Depth Grids



### **Project Timeline**

## Kick-off Meeting and Initial Community Feedback: [TODAY!]

### Data Development Work: [Now until Summer of 2025]

- Base Map
- Topographic Data
- Field Survey
- Develop Hydrologic and Hydraulic Models
- Floodplain Mapping

### Flood Risk Review Meeting:

[~April 2025]

 Your review and feedback on the draft maps

### Project Timeline, continued

Community comments will be addressed

Public review of the draft mapsIncludes Public

Open House

### **Preliminary Map Products**

Preliminary DFIRM
 Community
 Coordination Meeting

Post-Preliminary Processing









### Key Takeaways

### Floodplain Mapping Projects take time

Your involvement in this process will result in better flood information for your community

### DON'T HESITATE TO CALL, WE ARE HERE TO HELP



### Online Project Information

### **Project Website**

- Scoping Maps, Project Timeline, Meeting Presentations, Newsletters, Technical Reports, Web Review Map
- https://agriculture.ks.gov/divisions-programs/dwr/floodplain/mapping/mappingprojects/lists/mapping-projects/lower-middle-arkansas-custom-watershed


### Web Review Map: <a href="https://gis2.kda.ks.gov/gis/barton/">https://gis2.kda.ks.gov/gis/barton/</a>

- Provide comments on areas impacted by past floods, community needs, etc.
- Review of floodplain data

### **Story Maps**

"Floodplain Current": Mapping Process 'Nuts and Bolts'

### We are doing similar work across Kansas...





### **BFE Portal**

For Zone A floodplains, you can request BFE data. Keep in mind, BFE data is subject to change.

TZ					
Lansas Department of Agriculture	Kansas	Base	Flood	Elevation	Portal
Home	About	Help			
Portal Registration					
First Name					
Last Name					
User name					
Title					
Phone					
Email Address					
Address					
City					
Zip					
State	Kansas		~		
		Ro	egister		





### Contacts

FEMA – Region VII

**Dawn Livingston**Regional Project Officer
dawn.livingston@fema.dhs.gov

**KDA-DWR** 

Joanna Rohlf, CFM, GISP Floodplain Mapping Coordinator joanna.rohlf@ks.gov (785) 296-7769

William Pace, CFM
Floodplain Mapping Specialist
william.pace@ks.gov (785) 296-5440

**WSP** 

Ben Rufenacht, PE, CFM
Project Manager / Engineer
ben.rufenacht@wsp.com (785) 471-9174

Erika Stanley
Sr. GIS Analyst
erika.stanley@wsp.com (785) 760-1311