








Your engagement in this process is important to the success of this project, so thank you for taking the time to be here today!





Kansas Department of Agriculture

Joanna Rohlf, CFM, GISP

Floodplain Mapping Coordinator

William Pace, CFM
Floodplain Mapping
Specialist

Patrick Bonine
Floodplain Mapping
Specialist

Tara Lanzrath, CFM
State NFIP Coordinator

Cheyenne Sun Eagle, CFM NFIP Specialist

FEMA – Region VII

Dawn Livingston

Regional Project Officer

WSP USA Environment & Infrastructure Inc.

Matt Long, PE, CFM
Project Manager

Erika Stanley
Sr. GIS Analyst



Today's Goals

Share details on the mapping project

Get initial feedback on modeling methods

Review future steps



Background

- Middle Smoky Hill Custom Watershed BLE Project
 - Kick-off Meeting: November 2020
 - Discovery Meetings and BLE Review:
 May 2021

Discovery Report

Middle Smoky Hill Custom Watershed HUCS 10260006, 10260007

Cities of Brownell, Bunker Hill, Collyer, Dorrance, Ellis, Ellsworth, Galatia, Gorham, Grainfield, Grinnell, Hays, Kanopolis, Liebenthal, McCracken, Park, Russell, Schoenchen, Susank, Victoria, WaKeeney, Wilson


Barton, Ellis, Ellsworth, Gove, Lincoln, Ness, Rush, Russell, Sheridan, Trego Counties

Report Number 01 May 2021



Background

- Current Effective Mapping for Ellsworth County is dated August 10, 2021.
 - Only a portion of the county was updated.
 - The update incorporated modeling from the Cow Watershed and the Lower Smoky Hill Watershed Flood Risk Projects.
- It was determined that updated modeling and mapping for the portion of Ellsworth County in the Middle Smoky Hill Watershed using newer Lidar and 2D modeling techniques, would be beneficial.



Definitions




Hydrology *How Much Water?*




Hydraulics
How High Will Water Get?












- Enhancements will be made to the BLE modeling that was performed.
 - Lidar, flown in 2018, will be used.
 - Comments made will be used to enhance the modeling.
 - Additional review/refinement of mesh will be done to improve accuracy of modeling.
 - Enhanced Zone A and Zone AE with Floodway on selected streams will include field measured structure data, as-built survey plans, and additional landuse refinements.





- The hydrology is built into the RAS modeling platform using excess rain-on-mesh modeling.
- HEC-RAS calculates the excess rainfall from an initial abstraction based on NRCS Curve Number methodology.
- Details added to 2D mesh as needed.
- Add detail to significant flood control dams as needed.
- Model flows will be compared to Kansas regression flows and gage (where available) for validation and calibration.




A Floodway is the area within the floodplain that must be reserved in order to discharge the base flood without cumulatively increasing the WSE by more than 1.0 foot.










There are 0 levees in the project area.





Ellsworth County 2023 Proposed Mapping Updates

Scoped Studies

New Zone A - Excess Rainfall on Grid

New Zone A studies will be developed for these streams using 2D "excess rainfall-on grid" hydrology and 2D Hec-Ras hydraulics.

New Zone AE with Floodway - Gage

New Zone AE studies will be developed for these streams using 2D Hec-Ras hydraulics and hydrology calibrated to Gage model flows. Floodways will be developed. Field measured structure data will be incorporated into the modeling. BFEs will be shown on the maps.

New Zone AE with Floodway

New Zone AE studies will be developed for these streams using 2D Hec-Ras hydraulics and hydrology. Floodways will be developed. Field measured structure data will be incorporated into the modeling. BFEs will be shown on the maps.

New Static AE - Statistical Analysis


New Static Zone AE studies will be developed for these streams using statistical analysis to determine static water surface elevations.


New Enhanced Zone A - Excess Rainfall on Grid

New Enhanced Zone A studies will be developed for these streams using 2D "excess rainfall-on grid" hydrology and 2D Hec-Ras hydraulics. Field measured structure data will be incorporated into the modeling. BFEs will not be shown on the map.

Existing Studies - Will not be revised









18


Ellsworth:


Smoky Hill River






- Ellsworth:
 - K-14 Tributary
 - mapped as Zone AO in the effective FIS






- Wilson:
 - Wilson Creek
 - Smoky Hill River Tributary 29







Kanopolis:

Smoky Hill River





Ellsworth County





Field Survey Base Map Terrain Collaborative Partnerships **Development** Updated Hydrologic and Hydraulic Modeling Floodplain Mapping Draft FIRM Database FIRM & FIS Production Post-Processing Map Adoption

Project Tasks

- Field Survey
- Base Map and Topography Preparation
- Hydrologic and Hydraulic Modeling
- Floodplain Mapping
- DFIRM and FIS Production
- Post-Preliminary

We are about to begin the modeling task

Data



- We will complete the engineering analysis previously described.
- Several rounds of reviews will be completed.
- We will develop your draft regulatory floodplain maps.
 - Also known as your Flood Insurance Rate Map (FIRM)
- We will develop your draft Flood Insurance Study (FIS).
- We will have a community review period and a public review period

Project Timeline

Kick-off Meeting and Initial Community Feedback: [TODAY!]

Data Development Work: [Now until the Summer of 2024]

- Base Map
- Topographic Data
- Field Survey
- Develop Hydrologic and Hydraulic Models
- Floodplain Mapping

Flood Risk Review Meeting:

[~March 2024]

 Your review and feedback on the draft maps

Project Timeline, continued

Community comments will be addressed

Public review of the draft mapsIncludes Public

Open House

Preliminary Map Products

Preliminary DFIRM
 Community
 Coordination Meeting

Post-Preliminary Processing









Key Takeaways

Floodplain Mapping Projects take time

Your involvement in this process will result in better flood information for your community

DON'T HESITATE TO CALL, WE ARE HERE TO HELP



Online Project Information

Project Website

- Scoping Maps, Project Timeline, Meeting Presentations, Newsletters, Technical Reports, Web Review Map
- https://agriculture.ks.gov/divisions-programs/dwr/floodplain/mapping/mappingprojects/lists/mapping-projects/middle-smoky-hill-custom-watershed

Web Review Map: https://gis2.kda.ks.gov/gis/ellsworth/

- Provide comments on areas impacted by past floods, community needs, etc.
- Review of floodplain data

Story Maps

- Project Info
- "Floodplain Current": Mapping Process 'Nuts and Bolts'

